

Name of the work: "Laying of Paver blocks, fixing of stainless steel fencing and construction of open parking space at CMERI Institute Campus."

### SCHEDULE

Item No.	Particulars of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
<b>1. Dismantling &amp; Demolishing</b>					
1.1	Demolishing cement concrete of nominal mix 1:3:6 or richer by manually/mechanical means including disposal of rubbish within 50 m lead as per the direction of EIC.	cum	12.00		
1.2	Demolishing brick work in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material as per direction of Engineer-in-charge.	cum	4.00		
1.3	Labour for taking out (from fencing) line of wire (galvanised, strand or barbed) by drawing the same out through holes in the body of the post or through holes formed by fixed staples. (Payment to be made on the length of the wire taken out.)	m	250.00		
1.4	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	sqm	825.00		
<b>2. Earth Work</b>					
2.1	Earth work in excavation in all kind of soil / bolder by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m or as directed by EIC, disposed earth to be levelled and neatly dressed.	cum	4.00		
2.2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	5.00		
<b>3. Brick work</b>					
3.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes, with Cement mortar 1:4 (1 cement : 4 coarse sand),	Cum	2.00		
<b>4. P. C. C. work</b>					
4.1	Providing and laying in position 1:2:4 (1 Cement : 2 Coarse Sand (Zone III) : 4 graded stone aggregate 20 mm nominal size) cement concrete of specified grade excluding the cost of centering and shuttering, all the work upto plinth level.	cum	2.00		

Shreya  
10-07-18

*[Signature]*

Name of the work: "Laying of Paver blocks, fixing of stainless steel fencing and construction of open parking space at CMERI Institute Campus."

### SCHEDULE

Item No.	Particulars of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
4.2	Providing and laying cement concrete in kerbs, steps and the like at or near ground level excluding the cost of centering, shuttering and finishing. 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	cum	12.00		
4.3	Centering & shuttering including strutting, propping etc & removal of form for : Kerb, Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	sqm	80.00		
<b>5. Finishing</b>					
5.1	Removing white or colour wash or existing paints by scrapping and sand papering and preparing the surface smooth including necessary repairing to scratches etc. complete.	Sqm.	350.00		
5.2	12 mm cement plaster of mix of mix 1:4( 1 cement : 4 fine sand).	Sqm	350.00		
5.3	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade. New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) on existing wall surface.	Sqm	50.00		
5.4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. two or more coat.	sqm	350.00		
<b>6. Paver Block</b>					
6.1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design, shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	sqm	1200.00		
6.2	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer- in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	sqm	600.00		

Shrestha  
10-01-12



Name of the work: "Laying of Paver blocks, fixing of stainless steel fencing and construction of open parking space at CMERI Institute Campus."

### SCHEDULE

Item No.	Particulars of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
6.3	Finishing with Epoxy paint (two or more coats) on concrete work at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.	sqm	900		
	<b>7. Stainless steel railing &amp; Steel Work</b>				
7.1	Providing and fixing stainless steel ( Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	kg	125.00		
7.2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	50.00		
				Total	
TOTAL Rs. (in words)					

Shukla  
10-07-12

80