

Name of the work: Fixing of Name Plate at 1st gate in CMERI colony premises

### SCHEDULE

Item No.	Particulars of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Steel work welded In gratings, frames, window grill, guard bar, flat, ladder, railings, brackets, <b>gates</b> and similar works with plates/ built up sections/ framed work including cutting, hoisting, fixing in position and providing MS hinge, if necessary and applying a priming coat of approved steel primer using structural steel etc. as required.	kg	90.00		
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade two or more coat.	sqm	3		
3	Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming grooves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but including the cost of silicon sealant), labour, scaffolding and all other incidental charges complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP). a) 3mm thick (0.25mm Al.+2.5mm LDPE +0.25mm Al. PVDF coating) Sq	sqm	9		
4	Providing & fixing of Hindi/English COLOUR COATED (by powder coating) Stainless STEEL LETTER. Mesurement for the payment shall be calculated as "height of each letter in inch" x "no of letters"	inch	340		
				Total	

*Shah*  
16/01/19